

grille inside the studio, due to the resonance of its natural frequency with that of the impulse sound created by the hand-clap. The grille was later replaced by a plastic grille and the resonance has since then disappeared.

- Completion period

The construction was completed within

18 days, with a cost of about RM50,000.00 or US \$ 13,500, including the air-conditioning system and electrical work, but excluding the recording equipment. The work was undertaken by Makin Bersatu Acoustic Construction Sdn Bhd.

Acknowledgement

The writer wishes to thank Mr. Jack Teo of Shiok Music Sdn Bhd for permission to publish this article. Thanks also go to Kejuruteraan Semangat Maju Sdn Bhd for lending their B & K Precision Sound Level Meter for the noise measurements. ♦